THE BANK OF MYSORE LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 6th September 1928, published under Article 141 of the Articles of Association.

LIABILITIES			ASSETS		
		Rs.			Rs.
To Capital Receipts	...	20,00,000	By Cash in Hand and at Bankers		31,29,848
,, Reserve Funds	...	16,00,000	,, Loans & Cash Credit Accounts		1,42,86,491
,, Public and other Deposits	...	2,17,27,626	,, Bills discounted...	...	3,31,901
,, Sundries	...	2,41,800	,, Investments ...	...	71,82,455
			,, Balance at Agencies	...	11,583
(Annas and pies omitted.)			,, Dead Stock ...	...	5,77,922
			,, Sundries ...	...	49,226
Total	...	Rs. 2,55,69,426	Total	..	Rs. 2,55,69,426

BANGALORE,
Dated 12th September 1928.

K. P. RAMASWAMIAH,
Offg. *Manager*.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

NOTIFICATION OF TENDERS.

Dated Mysore 9th Septmeber 1928.

Notice is hereby given that sealed tenders will be received in the Office of the Superintendent, Power and Lighting, Mysore by 2 P.M., on the 1st October 1928, for (1) constructing Superintendent's Quarters with out-houses, Garage, etc., (2) constructing two units of Operators' Quarters with out-houses, latrines, etc., at Mysore. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The works should be completed within four and six months respectively.

2. The plans, detailed estimates and conditions may be seen at the Office of the Superintendent, Power and Lighting, Mysore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be accompanied by a statement in the form annexed showing the rates in words and figures at which the different items will be executed.—

Description of work	Unit of work	Rate per unit

4. Tenders will be opened at 2 P.M., on the 3rd October 1928.

5. Percentages less than or above estimates rates will not be accepted.

6. Each tender must be accompanied by a deposit of Rs. 500 and Rs. 600 respectively in cash or Government Promissory Notes, as earnest money, and be superscribed as "Tender for constructing Superintendent's Quarters with out-houses, etc.', and "Tender for constructing two units of Operators' Quarters, etc.," separately.

7. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

8. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bonds, in default of which his tender will be considered as cancelled, and his earnest money will be forfeited.

9. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Superintendent's Office in due course.

10. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

11. On acceptance of one of the tenders, the earnest money on rejected tenders will be refunded.

12. The construction work should be started within a fortnight at least from the date of notification of the acceptance.

13. Specifications for work are those recognised by the Mysore Public Works Department and Marryots specification.

14. Water for the construction should be got at the contractor's own expense.

15. The contractor should bind himself by the conditions of the schedule of contract of the Electrical Department.

(1)

Statement showing the approximate quantities for constructing Superintendent's Quarters with Out-houses, garage, etc., at Mysore.

Serial No.	Particulars	Quantity		Unit
		Main building	Out-houses, etc.	
1	Earthwork excavation and filling in basement including a lead of 50 ft.	43	33	C.yd.
2a	Stone jelly in chunam concrete foundation 2 of jelly and one of surki;	641	...	C.ft.
b	Coursed rubble stone masonry in mortar foundation and basement.	1186	1431	,,
c	B. brick in clay superstructure	1890	1565	,,
d	Do mortar superstructure	671	500	,,
e	Do with centrings	98	...	,,
f	Stone slabs 6" thick roughly dressed and fixed in mortar.	164	96	S.ft.
g	Stone slabs 4" thick for pillars with paly cutting ...	...	43	,,
h	Do 3" thick for seats in latrine	...	4	,,
i	B. brick in mortar pillars 1 1/8' x 1 1/8' by 7 ft. with plastering, etc., complete.	6	...	each
j	Plain brick cornice 6" projection	97	41	R.ft.
k	Mortar pointing with lining	2·60	2·50	Sqrs.
l	Plastering with mortar 2 coats	55·11	41·50	,,
m	White and colour washing 2 coats	57·71	44·00	,,
n	Binding 1 1/8' x ¾' over roof brick in mortar with plastering complete.	60	28	R.ft.
p	Chunam border 6" x 3" over verandah roof ...	21	14	,,
q	B. brick in mortar coping 9" deep	...	63	,,
r	Tarring 2 coats	...	0·32	Sqrs.
3a	First Class Mangalore tile flooring on 3" concrete and cement pointed.	14·38	6·75	,,
b	Flooring with Cuddapah slab on 3" concrete and cement pointed.	...	1·50	,,
c	Flooring on 3" concrete and cement plastering ½" thick.	...	0·25	,,
d	Cement plastering ½" thick	...	0·40	,,
4a	Roofing with First Class Mangalore tiles on T. W. reepers 2" x 1".	21·21	13·50	,,
b	Ridge tiles set in mortar and cement pointed ...	48·5	64	,,
c	Ventilating tiles	...	8	each
d	G. I. eave guttering 6" x 6" 22 B.W.G.	99	...	R.ft.
e	Rain water down pipes 3" dia. 24 B.W.G. ...	60	...	,,
5a	Teak wood work with wood oiling	101·85	58	C.ft.
b	T. W. door panelled 1¼" th. shutters with bolt, hinges, etc., complete frames 4" x 3½".	293	...	...
c	T. W. windows with panelled shutters outside and glazed shutters inside with iron bars ⅜" dia. and fittings, etc. frames 3¾" x 3" vide drawing M. 147.	68	...	...

Serial No.	Particulars	Quantity		Unit
		Main building	Out-houses etc.	
5d	T. W. windows with bottom shutters 1″ thick with iron bars and fitting frames 3¾″ x 3″ *vide* drg. No. M. 147.	...	60	R.ft.
e	T. W. glazed ventilators, shutters 1″ thick with iron bars, etc., 3″ x 3″ *vide* drg. No. M. 147.	63	...	...
f	T. W. battened door 1¼″ thick shutters with hinges, bolts, etc., frames 4″ x 3½″ vide drg. No. M. 147.	...	95	...
g	T. W. cup board with panelled shutters and shelves with hinges, etc., frames 3¾″ x 3″ *vide* drg. No. M. 147.	72	60	...
h	Fixing clamps to doors and windows	52	20	Each
i	Door fitted with plain G. I. shutters with bolts, hinges, etc., frames 6″ x 6″ *vide* Drg. No. M. 147.	...	72	S.ft
j	Plain T. W. Eave boarding 9″ x 1″	63·5	131	R.ft.
k	T. W. planks 1″ thick for shelves screwed on to wooden peg 3″ square fixed in wall complete with wood oiling.	32	30	S.ft.
l	Chaculate painting 2 coats	1200	10·50	Sqr.
6	Constructing chimneys	...	2	each
7	Fixing W. I. drain pipes 1″ dia. and 18″ long in walls.	7	5	,,
8	Fixing mortar and pestle	...	1 set	...
9	Constructing sinks in bath rooms 3′ x 2′... ...	2	2	,,
10	Constructing side veraudah to the Superintendent Quarters as per details below.	...	Qy.	Unit
1	Earthwork excavation and filling in basement ...	...	6	Cyd.
2a	Stone in mortar, foundation and basement ...	...	258	C.ft.
b	Burnt brick in clay, superstructure	...	76	,,
c	Burnt brick in mortar, pillars complete	...	4	each
d	Stone slabs 6″ thi. roughly dressed	...	6	S.ft.
e	Pointing with mortar with lining	...	1·01	Sqrs.
f	Plastering with mortar	...	2·02	,,
g	White and colour washing 2 coats	...	3·03	,,
h	Burnt brick in mortar coping 9″ deep	..	11	R.ft.
3	First Class Mangalore tile flooring on 3″ concrete and cement pointed.	...	2·61	Sqr.
4a	First Class Mangalore tile roofing on T. W. reepers 2″ x 1″.	...	3·59	,,
b	Ridge tiles set in mortar and cement pointed ...	...	28	R.ft.
5a	Teak wood work with wood oiling 2 coats ...	...	21·81	C.ft.
b	Teak wood eave boarding 9″ x 1″ plain	...	56	R.ft.
c	Chacolate painting 2 coats	...	0·42	Sqrs.

(2)

Constructing two units of Operators' Quarters with Out-houses, latrines, etc., at Mysore.

Serial No.	Particulars	Quantity		Unit
		Main building	Out-house	
1	Earth work excavation ordinary and gravelly soil including a lead of 50 feet.	42	19	Cyd.
2a	Concrete stone jelly in mortar foundation 2 of jelly and 1 of mortar.	384	...	..
b	Coursed rubble stone masonry in mortar foundation and basement.	1122	703	...

Serial No.	Particulars	Quantities		Unit
		Maine building	Out houses, etc.	
c	B. Brick in clay superstructure	20·25	837	...
d	B. brick in mortar superstructure	426	345	...
e	B. brick in mortar arch work with centrings ...	76	40	...
f	Stone slabs 6″ thick roughly dressed and fixed in mortar.	51	22	Sq.ft.
g	Pillars, burnt brick in mortar with plastering, etc., complete 1 1/8 x 1 1/8 x 7′ 10½″.	6	...	each.
h	Pointing with mortar with lining	2·05	1·42	Sqrs.
i	Plastering with mortar 2 coats	41·84	25·80	,,
j	White and colour washing 2 coats	44	27·22	,,
k	Plain brick cornice 6″ projection	97	32	R.ft.
l	Chunam borders over verandah roof 6″ x 8″, 6″ x 3″ and 4″ x 3″.	50	...	...
m	Binding wall 1 1/8′ x ¾′ brick in mud and chunam plastered.	61	30	...
n	Stone slabs 3″ thick roughly dressed and fixed in mortar.	...	4	Sft.
o	Coping of brick in mud and plastered complate 9″ thick.	...	63	R.ft.
3 a	First Class Mangalore tile flooring on 3″ concrete brick jelly in lime mortar and cement pointed.	8·83	3·07	Sqrs.
b	Flooring with 3″ brick jelly in lime mortar concrete and cement plastered ½″ thick	...	0·27	,,
c	Cement plastering ½″ thick	...	0·36	,,
4 a	First Class Mangalore tile roofing on T. R. 2″ x 1″ ...	13·86	6·33	,,
b	Ridge tiles set in mortar and cement pointed ...	33	33	R.ft.
c	Ventilating tiles.	...	6	Each
d	T. W. work with wood oiling two coats	62·52	22·58	C.ft.
e	Plain T. W. eave boarding fixed 9″ x 1″ ...	73	...	R.ft.
f	T. W. panelled door 1½″ shutters with fittings, etc., frames 3½″ x 4″ as per dug. No. M. 147.	169	...	S.ft.
g	T. W. battened doors 1¼″ shutters with fittings, etc., 4″ x 3½″ frames as per drg. No. M. 147.	..	115·5	,,
ig	T. W. windows with panelled shutters 1″ thick inside with iron bars and fixtures, etc., complete frames 3¾″ x 3″ as per drg. No. M. 147.	84	...	,,
i	T. W. battended windows 1″ thick shutters with iron bars and fixtures, etc., complete frames 3¾″ x 3″ as per drg. No. M. 147.	...	36	
j	T. W. glazed ventilators with iron bars frames 3″ x 3″ as per drg. No. M. 147.	30	6	,,
k	T. W. cupboards with three shelves and panelled shutters 1″ thick frames 3¾″ x 3″ *vide* drg. No. M. 147.	24	...	...
l	Painting with chacolate paint two coats ...	7·36	3·83	Sqr.
m	T. W. planks 1″ thick, for shelves screwed on to wooden pegs 3″ x 3″ fixed in wall.	38	30	S.ft.
n	Fixing iron clamps to doors and windows ...	34	16	Each
5	Constructing sinks in bath room 3′ x 2′ ...	1	2	
6	Providing mortar and pestle	...	1	,,
7	Tarring two coats	...	0·36	Sqr.
8	Fixing W. I. drain pipes 1″ dia. 18″ long in rooms ...	5	4	
	The above are for one unit. For two units double these quantities.			

C. SITARAMIAH,
Superintendent, M. P. L..